

NASA/CR-97-

206459

Final



Hamilton Standard
A United Technologies Company

TINH

JN-34-512

271

125738

Water Processor and Oxygen Generation Assembly

Contract H-29387D

Final Report

December 5, 1997

Prepared for
NATIONAL AERONAUTICS AND SPACE ADMINISTRATION
MARSHALL SPACE FLIGHT CENTER
HUNTSVILLE, ALABAMA

Prepared by
UNITED TECHNOLOGIES CORPORATION
HAMILTON STANDARD SPACE SYSTEMS INTERNATIONAL, INC.
WINDSOR LOCKS, CONNECTICUT 06096

Prepared by:

John Bedard
John Bedard

Approved by:

D. D. O.
Engineering Manager (OGA)

Approved by:

D. B. R.
Engineering Manager (WP)

Approved by:

M. J. Stumpf
Program Manager

1.0 Introduction:

This report documents the results of the tasks which initiated efforts on design issues relating to the Water Processor (WP) and the Oxygen Generation Assembly (OGA) Flight Hardware for the International Space Station. This report fulfills the Statement of Work deliverables requirement for contract H-29387D.

The following lists the tasks required by contract H-29387D:

1. HSSSI shall coordinate a detailed review of WP/OGA Flight Hardware program requirements with personnel from MSFC to identify requirements that can be eliminated without affecting the technical integrity of the WP/OGA Hardware.
2. HSSSI shall conduct the technical interchanges with personnel from MSFC to resolve design issues related to WP/OGA Flight Hardware.
3. HSSSI will initiate discussions with Zellweger Analytics, Inc. to address design issues related to WP and PCWQM interfaces.

2.0 Major accomplishments during the reporting period:

2.1 Initial requirements review:

HSSSI conducted several internal reviews of the WP/OGA Flight Hardware technical and programmatic requirements. The result of these reviews was a list of questions, issues and assumptions.

HSSSI has submitted this list to MSFC that will serve as a basis of generating the specification and ICD requirements for the WP/OGA Flight Hardware. Within this list are recommendations and assumptions to provide reduced requirements without effecting the integrity of the hardware.

A study of data items (DI) that are currently required on several other NASA programs has been conducted. This list along with HSSSI's recommendations for the flight program DIs will be provided at the TIM scheduled in December. The goal is a list of DIs that will minimize the cost to the program.

2.2 Technical Interchange Meeting

A Technical Interchange Meeting (TIM) was conducted at MSFC on November 19, 1997. Attachment I is a copy of the slide presented. The presentation covered the following topics: program schedule milestones, pre-start tasks, specification and ICD questions / issues, MSFC SOW, Data Items, EEE Parts, and OGA Power Supply. A near term schedule was developed and agreed to at the meeting and is provided in figure 1.

As a result of the TIM an Action Item List was generated and is in figure 2

OGA & WP Near Term Schedule

- Contract 1 ATP 11/7/97
- Technical and Business Meeting at MSFC 11/19/97
- TIM #1 at MSFC for Requirements Development 12/16-18/97
- TIM #2 at SSI for Requirements Development 1/13-15/98
- Draft B1 System Specifications & CEI Specifications 1/15/98
- Draft Interface Control Documents 1/15/98
- Baseline System Schematics 2/24/98
- Draft Statement of Work 3/1/98
- Program Requirements Review at MSFC 2/24-26/98

FIGURE 1

WATER PROCESSOR/OGA ACTION ITEM LIST

TECHNICAL MEETING 11/19/97

ACTION ITEM NO.	DESCRIPTION	DU^E DATE	PERSON RESPONSIBLE	STATUS
1	Provide spec software (Doors) info to MSFC	12/1/97	B.Kundrotas	Closed 11/21/97
2	SSI recommendation on Program Data Items including DI description	12/15/97	D. Cloud/D. Parker	
3	MSFC response in writing on spec and ICD issues/questions	12/15/97	B. Bagdigian	
4	Draft "SOW" for OGA Power Supply	12/15/97	D. Cloud	

FIGURE 2

2.3 Zellweger Analytics, Inc.

HSSSI has initiated discussions with Zellweger Analytics, Inc. to address design issues related to WP and PCWQM interfaces. HSSSI and Zellweger conducted telephone conversations on Nov. 6 and 13, 1997 to review program status and history. These telecons were in preparation for TIM held at MSFC on Nov. 20, 1997 with HSSSI and MSFC in attendance. The minutes of the meeting are provided in Attachment III. Please note that financial data contained in minutes have been removed from Attachment III for this submittal. Topics included in Zellweger's presentation were PCWQM status, schedule, design issues, manpower requirements, and a review of the recent trade study efforts funded by MSFC. In addition, Zellweger discussion included the iodine and conductivity sensor assembly (CISA) program conducted for Boeing following the PCWQM program shutdown. This assembly was investigated for potential implementation into the WP and OGA system designs.

3.0 Additional Tasks

During this contract period, HSSSI has initiated additional tasks to support the items in the Statement of Work:

1. Internal schematic reviews on both the WP and OGA have been initiated.
2. Computer models of the WP and OGA schematics have been initiated.
3. Review of RIDs from WP PDR held in March, 1992.
4. Program Planning Tasks such as development of the initial program organization, identifying preliminary work breakdown structures, configuration control planning, and data rights reviews.

4.0 Conclusion

HSSSI has fulfilled the requirements of the Statement of Work for Contract H-29387D. The dialogues initiated between MSFC, HSSSI and Zellweger have been informative and productive..

ATTACHMENT I

Oxygen Generator Assembly

and

Water Processor

Technical Meeting

at

Marshall Space Flight Center, Huntsville

November 19-20, 1997

OGA & WP Technical Meeting

List of HS Attendees

Dale Cloud - Project Engineering Manager (OGA) (11/19)
Dave Parker- Project Engineering Manager (WP) (11/19-20)
Mike O'Toole - Lead Electrical Design (11/20)
Lynn Rollins - Purchasing Manager (11/20)
Mike Stanley - Program Manager (11/19-20)
Rich Mason - Field Engineer (11/19)
Mike Tosca - Subcontract Program Manager (11/19-20)
Kevin Grohs - Contracts (11/19)
Dexter Wheelock - Financial (11/19)
Donna Grossman - Mechanical Design (11/19-20)

OGA & WP Technical Meeting

Agenda

Wednesday, November 19-1:00-4:30

- Organization Charts (MFSC & HS)
- Schedule Milestones
- Pre-Start Tasks
- Specification Issues
- ICD Issues
- MSFC SOW/ Preliminary List of Data Items
- EEE Parts
- OGA Power Supply
- System Schematics
- OGA Tour at 4755

OGA & WP Technical Meeting

Agenda

Thursday, November 20-8:30-4:00


Zellweger Analytic Presentation

- PCWQM
 - Status
 - Design
 - Issues
 - Schedule
- I2/Conductivity Sensor
 - Status
 - Design
 - Issues
- Contract Issues (HSSSI & Zellweger)
- Manpower (HSSSI & Zellweger)

(HS- D. Parker, L. Rollins, M. Stanley, M. O'Toole, M. Tosca, D. Grossman)

OGA & WP Technical Meeting

Preliminary Organization Chart



OGA & WP Technical Meeting

Near Term Schedule

- Contract 1 ATP 11/7/97
- Technical and Business Meeting at MSFC 11/19/97
- TIM #1 at MSFC for Requirements Development _____
- TIM #2 at SSI for Requirements Development _____
- Draft B1 System Specifications _____
- Draft Interface Control Documents _____
- Finalize System Schematics _____
- Issue Statement of Work _____

OGA & WP Technical Meeting

Schedule Milestones

- Contract 1 ATP 11/7/97
- WP GLS CR&D Contract ATP 11/97
 - Technology Trade Study
 - Hardware Procurement and Test
 - Deliver Prototype Hardware to MSFC 7/98
- System Requirements Definition 11/97-2/98
- Receive RFP 2/98
- Flight Contract ATP 7/98
- OGA PDR 8/98
- WP Delta PDR 8/98
- ISS WP vs JSC ALS Decision Point 1/99
- CDR 3rd Quarter 99
- System Delivery 7/01
- Node 3 Launch 7/02

OGA & WWP Technical Meeting

Pre-Start Tasks

Contract 1 & 2

- Program Planning
- System Specification
- ICD
- Initial Design Tasks

OGA & WP Technical Meeting

Pre-Start Tasks

- Program Tasks -Contract 1
 - Internal Kickoff Meeting November 13, 1997
 - PD for Contract 1
 - PDR Info and RID Review (WP)
 - Final Report, December 1997

OGA & WP Technical Meeting

Pre-Start Tasks

- Program Planning-Contract 2
 - Issue Program Directives
 - Proprietary Notification List
 - Detailed Manpower Plan
 - Continue Detailed Schedule Planning
 - Finalize WBS Structure
 - Documentation-POP, Q Plan, M&P Plan, Mfg Plan, etc.

OGA & WP Technical Meeting

Prestart Tasks

- System Specifications-Complete Jan 1998
 - TIM at MSFC for Requirements Review-Contract 1
 - Resolve AI's from TIM-Contract 1
 - TIM at SSI for specification development-Contract 2
 - Write and issue B1 system specification-Contract 2
 - Weight, power and volume studies, for specification input-Contract 2

OGA & WP Technical Meeting

Prestart Tasks

- Interface Control Document (ICD)- Complete Feb 1998
 - TIM at MSFC ICD Issues Review-Contract 1
 - Resolve AI's from TIM-Contract 1
 - Assist MSFC in ICD preparation-Contract 2

OGA & WP Technical Meeting

Prestart Tasks-OGA

- Initial Design Tasks
 - Review OGA System Schematic-Contract 1
 - Finalize OGA System Schematic, Nov 1997-Jan 1998-Contract 2
 - Safety Review
 - Determine location of I/X bed
 - Computer model for system dynamics
 - Component Specifications Dec 1997-Jan 1998-Contract 2
 - Revise mini specifications
 - Bellows tanks

OGA & WP Technical Meeting

Prestart Tasks-OGA

- Initial Design Tasks (continued)
 - Preliminary Parts and Drawings Lists, Jan 1998-Contract 2
 - Motor Controller Topology & Packaging Study, Nov 1997-Jan 1998-Contract 2
 - Controller Evaluation and Make Buy Study, Nov 1997-Jan 1998-Contract 2
 - Power Supply Interface Definition-Contract 1

OGA & WP Technical Meeting

Prestart Tasks-WP

- Initial Design Tasks
 - Review WP System Schematic-Contract 1
 - Finalize WP System Schematic, Nov 1997-Jan 1998-Contract 2
 - Liquid and gas sensor alternate concepts
 - Waste water and delivery schematic trades
 - Scrubber for MLS gas outlet
 - Removal of the sterilization ORU
 - Evaluate addition of a flow sensor or monitor tank quantity
 - Evaluate alternate location of conductivity sensors
 - Computer model for system dynamics

OGA & WP Technical Meeting

Prestart Tasks-WP

Initial Design Tasks (continued)

- Component Specification, Dec 1997-Jan 1998-Contract 2
 - Revise mini specifications
 - Bellows tanks
- PDR Status/Design, Nov-Dec 1997-Contract 2
 - Review RID status
 - Develop list of PDR open issues and review for current action
- Preliminary Parts and Drawings Lists, Jan 1998-Contract 2
- Motor Controller Topology & Packaging Study, Nov 97-Jan 1998-Contract 2
- Controller Evaluation and Make Buy Study, Nov 97- Jan 1998-Contract 2

OGA & WP Technical Meeting

Prestart Tasks-WP

- Initial Design Tasks
 - PCWQM-Zellweger CDR Presentation, Dec 1997
 - Review CDR and program documentation -Contract 1
 - Attend TIM/CDR presentation at MSFC, Nov 20, 1997-Contract 1
 - Quality survey of Zellweger, Dec 1997-Contract 2
 - TIM at Zellweger's to continue technical/programmatic discussions, Dec 1997-Contract 2

OGA & WP Technical Meeting

Specification Issues

- See attached sheets

QUESTIONS/COMMENTS FOR MSFC
11/18/97

SPECIFICATION QUESTIONS/COMMENTS:

- Utilize the latest revision SSP documents. Some of these suggested documents are:
 - Electrical power - SSP 30482, Vol. 2
 - Materials/Processes - SSP 30233
 - EEE Parts - SSP 30312 & SSP 30423
 - Electromechanical Radiation - SSP 30237 (Testing - SSP 30238)
 - Grounding - SSP 30240
 - Bonding - SSP 30245
 - Cable/wire Design - SSP 30242
 - Workmanship - NHB series
 - Human Performance/Human Engineering - SSP 50005
 - Structural - SSP 30559
 - Fracture Control - SSP 30558
 - Reliability - Ex: FMEA/CIL SSP 30234
 - Safety - Ex.: Safety Hazard Analysis SSP 30309
- What are the Classification of Characteristics requirements?
- Are we required to use the Boeing quick disconnects?
- We are assuming the edge break (or radii) requirements of SSP50005 (not NASA-STD-3000).
- Does MSFC have any hydrogen safety requirements, design standards, explosion pressure factors, and/or ventilation requirements?
- What are the maintenance requirements?
- Are blind-mate quick disconnects and/or electrical connectors acceptable?
- Does MSFC have any preferred or recommended common hardware, such as:
 - slides
 - quick disconnects
 - valves
 - sensors
 - flex lines
 - electrical connectors
 - fasteners
- Are there any fastener preload/torque analysis requirements?
- HS to have the capability to define the verification methodology for each shall statement subject to MSFC approval
- Need operational timeline profiles for water usage on ISS.
- HS recommends NC-55 for acoustic requirement. Rack panels provide attenuation against the NC-50 station requirement.
- How will the systems be shipped to MSFC (as a system or as ORU's)?
- MSFC to define minimum expendable life.
- Establish performance requirements when the system is exposed to low ambient pressure 9.0 Psia and 10.0 to 10.6 psia operation for 1095 days.
- Verify inlet waste water system filtration level is 100 micron.

QUESTIONS/COMMENTS FOR MSFC

11/18/97

- HS will develop specifications utilizing MIL-STD-490.
- HS is assuming the following failure tolerance:
 - 0 fault tolerant for function (i.e. fail safe)
 - 1 fault tolerant for critical failures
 - 2 fault tolerant for catastrophic failures
 - 1 fault tolerant for marginal failures
- What are the weight, power, volume requirements for each system?

RELIABILITY/SAFETY QUESTIONS:

- What is the functional criticality of the systems?
- If the system fails, what actions would be taken? What are the backups?
- Will the controller be considered one fault tolerant under the proper design conditions? (such as watch dog timers, periodic ram/rom tests, separation of critical redundant signals)
- Is there a space station atmospheric monitor that would backup the OGA so far as detecting hydrogen below the lower explosive limit?

QUESTIONS/COMMENTS FOR MSFC
11/18/97

MECHANICAL DESIGN QUESTIONS/COMMENTS

Rack questions/comments:

- What is the exact double rack configuration? We need drawings ASAP.
- Where are the rack keep-out volumes?
- Where are the allowable attachment points?
- What size and configuration are the attachment points?
- What is the total load bearing capacity of the rack? We need this value for racks both with and without the centerpost.
- Is there a load limit per post?
- Is there a load limit per attachment bolt?
- Where is the interface panel (at the stand-off) and what is its configuration? What are the electrical and fluid interface configurations?
- What is the expected rack structure deflection (i.e., what clearance is required between the hardware and the rack)?
- Is there a CG location requirement?
- What electrical bonding provisions are provided in the rack?

Packaging questions/comments:

- Our assumption is that if an Avionics Air Assembly is required, it is not part of our packaging volume.
- Besides front access, what other maintenance access is allowed?
- Is liquid cooling available? What heat rejection capacity is available?
- How much heat can be dumped into the rack?
- We will supply all ducting, tubing, and harnessing required to interface from the interface panel and/or the Avionics Air Assembly to our hardware.

Structural questions/comments:

- What is the natural frequency requirement?
- What are the quasi-static loads?
- What are the random vibration loads?
- Is there a required method for load combination?
- What are the safety factor requirements?
- What are the fracture control requirements?
- Is there a problem with tying across rack corner posts (side-to-side or front-to-back)?
In this case, what loads from the rack are inputted into our ORU's?
- Who is responsible for the structural analysis of our ORU's as part of the rack?

OGA & WP Technical Meeting

ICD Issues

- See attached sheets

QUESTIONS/COMMENTS FOR MSFC
11/18/97

Water Processor Interfaces:

Ambient Air

Temperature Range

Pressure Range

Dew Point Range

Oxygen Concentration Range

Nitrogen (In) (Water Storage ORU) - approximately .5 lbs per day required

Temperature Range

Pressure Min.

Flow Rate Max.

Dew Point Range

Waste Water (In) (Waste Water ORU)

Temperature Range

Pressure Range

Flow Rate

Average Lb/min

Peak Lb/min

Quality (Contaminants/constituents)

Gas Vent (Out) (Waste Water ORU)

Constituents/properties

Physical connection

Oxygen Supply (In) (Catalytic Reactor ORU)

Pressure Min.

Flow Rate Max.

Gas Vent (Out) (Gas Separator ORU)

Physical

Ambient Pressure Range

Dew Point Range

Product Water Supply (Out) (Water Storage ORU)

Back Pressure

Water Quantity Required

Electrical Power

SSP 30263:002 RPCM Requirements

SSP 30482, Vol. 1 and Volume 2 Power Requirements

QUESTIONS/COMMENTS FOR MSFC
11/18/97

Data Bus (1553)

Assembly Commands

INITIALIZE	HARD STOP
STANDBY	BIT EXECUTION
OPERATE	REPROCESS
SHUTDOWN	OVERRIDE

Assembly Sensor/Status Feedback (as a minimum)

Fault Status/Isolation (As processed within the embedded controller)

Non-operating Environments by Phase (Transportation, Storage, Prelaunch, Launch, etc)

Temperature	Pressure	Humidity
Vibration	Acceleration	Shock
Acoustics		

QUESTIONS/COMMENTS FOR MSFC
11/18/97

Oxygen Generator Interfaces:

Ambient Air

Temperature
Pressure
Relative Humidity
Dew Point
Oxygen Concentration

Nitrogen (In)

Temperature
Pressure
Flow Rate
Dew Point
Quality (Contaminants/constituents)

Feed Water (In)

Temperature
Pressure
Flow Rate
Quality (Contaminants/constituents)

Coolant Water (In)

Temperature
Pressure
Flow Rate
Quality (Contaminants)

Coolant Air (In) (If any)

Temperature
Pressure
Flow Rate
Dew Point

Hydrogen Supply (Out)

Back Pressure

Hydrogen Vent (Out)

Allowable Purge Gas Mix
Continuous or Time Restricted
Rate, Maximum
Back Pressure

QUESTIONS/COMMENTS FOR MSFC
11/18/97

Oxygen Supply (Out)

 Back Pressure

 Production Rate

Electrical Power (From RPCM to PSM and rest of assembly)

 SSP 30263:002

 SSP 30482, Vol. 1 (Interface C)

Data Bus (MIL-STD-1553B)

 DSBG 9549 ??

Assembly Commands (Fixed duty cycle and production rate)

 IMMEDIATE SHUTDOWN

 ON

 OFF

 MANUAL

Assembly Sensor/Status Feedback

 Oxygen Pressure

 Cell Current

 Cell Voltage

 Conductivity Sensor (Output)

 Fault Status/Isolation (As processed within the embedded controller)

Power Supply

 Input Power

 Output Power

 Control/Feedback Signals

 Mechanical Interfaces

Non-operating Environments by Phase (Transportation, Storage, Prelaunch, Launch, On-orbit, Return-to-earth)

 Temperature

 Pressure

 Humidity

 Vibration

 Acceleration

 Shock

 Acoustics

OGA & WP Technical Meeting

MSFC SOW and Data Items

OGA & WP Technical Meeting

EEE Parts

- Reliability Level
- Source


OGA & WP Technical Meeting

OGA Power Supply


- GFE

WATER PURIFICATION (WP) SIMPLIFIED SCHEMATIC

11/18/97



SPE[®] OXYGEN GENERATOR ASSEMBLY (OGA) FLUID SCHEMATIC (DOME)



[®]SPE is a registered trademark of Hamilton Standard Division of United Technologies Corporation

ATTACHMENT II

Zellweger Analytics, Inc.
100 Park Avenue
League City, Texas 77573 USA

Tel: 281 332 2484
Fax: 281 554 6795



November 25, 1997
ZA971633

Hamilton Standard
Space Systems International, Inc.
1 Hamilton Road
Windsor Locks, CT 06096-1010
Tel: 860-654-6000

Attention: Ms. Lynn M. Rollins, Purchasing Manager; M/S 1A-3-Z65

Subject: Minutes, International Space Station (ISS) Process Control Water Quality Monitor (PCWQM) Program Technical Interchange Meeting (TIM); November 20, 1997.

Dear Ms. Rollins,

The subject ISS PCWQM TIM Minutes and a copy of ZALC's TIM presentation package are enclosed and are being submitted to you for your information and further distribution as you deem appropriate. ZALC is in the process of working the action items we were assigned at this meeting and will provide responses to you as they become available.

Should you have any questions regarding any of the above material, please contact the undersigned at 281-332-2484, Ext. 57.

Regards,


Ken Smith
Program Manager

cc. (Ltr. & Minutes only)

Mr. Donald L. (Layne) Carter, Mail Stop ED-62
George C. Marshall Spaceflight Center
Marshall Space Center, AL 35812

cc. m. tosua
D. Carter /
D. Glassman
m. ctoue

Subject: Meeting Minutes, International Space Station (ISS) Process Control Water Quality Monitor (PCWQM) Introductory Technical Interchange Meeting (TIM)

Location: Building 4610, Room 5015; George C. Marshall Space Flight Center, Marshall Space Center, AL

Date/Time: November 20, 1997 / (8:30 a.m. to 5:30 p.m.)

Attendees: National Aeronautics and Space Administration/Marshall Space Flight Center (NASA/MSFC):

Bob Bagdigan, ED62; Layne Carter, ED62; Jim Reuter, OB3

Hamilton Standard Space Systems International (HSSI), Inc.

Windsor Locks, CT - Donna Grossman, Mechanical Engineer; Dave Parker, Project Manager; Lynn Rollins, Purchasing Manager ("Buyer"); Mike Stanley, Program Manager for Water Processor; Michael Tosca, Major Subcontracts Manager.

Huntsville, AL - Rich Mason, Site Technical Representative; Mike O'Toole, Electrical Engineer;

Zellweger Analytics League City (ZALC):

Dale Dougherty, Chief Engineer; Ken Smith, Program Manager

Purpose: The purpose of the meeting was to introduce key members of the NASA/MSFC, HSSI and ZALC ISS Water Processor (WP) and PCWQM program teams to one another and provide a background and overview of the PCWQM program. Historical prospective was provided for both PCWQM and ICSA Programs as well as discussions for current and future work. Previous telecons regarding restarting the PCWQM contract were held 11-6-97 and 11-13-97.

The was meeting was opened by Mr. Layne Carter who, in turn, introduced the other meeting attendees. These introductions provided a "voice-with-a-face" association and some discussion ensued delineating the rolls these individuals will have in the Water Processor and PCWQM programs. Next, Mr. Dave Parker gave some introductory remarks, presented a meeting Agenda and Schedule, and turned the meeting over to Mr. Ken Smith.

Mr. Smith began with a PCWQM Programmatic presentation (attached) providing Schedule and Manpower charts for the next three years. Discussion took place asking for clarifications where necessary and when Hamilton Standard anticipates funding which can then be used to begin ZALC's PCWQM efforts. Currently a sole source justification describing why Hamilton Standard is the only qualified Water Processor vendor to NASA is being executed by MSFC/NASA. It is anticipated that a Letter Contract between MSFC and HSSI will be complete on or before

January 1, 1998, at which point HSSSI can formally provide same to ZALC.

Dale Dougherty then went through a PCWQM and ICSA history presentation (attached) describing how the design evolved to the PCWQM-SEU, then to ICSA. The work done for ION Systems was presented and discussed as well as what technical tasks need to be addressed in the near future. Discussion ensued as to why the SEU design should be abandoned in lieu of a 'stand alone' PCWQM and all concurred that the latter, if it can be designed feasibly, makes the most sense.


MSFC electrical design engineers joined the meeting at 1:30 to review the UV Ballast Supply requirements so they can determine if they can provide such a supply to us for incorporation into the PCWQM, as GFE.

Following the UV Power Supply segment of the meeting, Mr. Smith went over the Rough Order of Magnitude (ROM) pricing and related assumptions that ZALC had developed and submitted to NASA/MSFC previously, based on preliminary program requirements and delivery schedules provided by NASA. ZALC's CY98 PCWQM Program manpower figures and pricing data were provided formally to Ms. Lynn Rollins in response to her earlier request for same.

Upon completing the presentation and discussion segments of the meeting, participants adjourned to Bldg. 4655 where they were given a brief tour and overview description of the ECLSS Stage-10 Test Setup by Mr. Layne Carter. The Stage-10 Water Processor (WP) and Process Control Water Quality Monitor (PCWQM) were the focus of this activity.

Action Items resulting from the subject meeting were as follows:

AI#	Assignee	Due Date	Action Item/Task
1	ZALC (DD, KS)	11-24-97	Provide copies of slides presented.
2	ZALC (DD)	12-01-97	Provide copy of UV Lamp drawing for MSFC electrical designers to review.
3	ZALC (DD)	01-15-98	Need Draft of a UV Ballast Power Supply SCD for MSFC
4	ZALC (KS,DD)	01-15-98	Review PCWQM-SEU RIDs from CDR and consider whether they are applicable or OBE.


Ken Smith, ZALC GPU Program Mngr


Dale Dougherty, ZALC Chief Engr

Dave Parker, HSSSI Project Mngr

Lynn Rollins, HSSSI Purchasing Mngr

OGA & WP Technical Meeting

Agenda


Thursday, November 20-8:30-4:00

Zellweger Analytic Presentation


- PCWQM
 - Status
 - Design
 - Issues
 - Schedule
- I2/Conductivity Sensor
 - Status
 - Design
 - Issues
- Contract Issues (HSSSI & Zellweger)
- Manpower (HSSSI & Zellweger)

(HS- D. Parker, L. Rollins, M. Stanley, M. O'Toole, M. Tasca, D. Grossman)

PCWQM PROGRAM HEADCOUNT BUILDUP CY-98




PCWQM PROGRAM HEADCOUNT CY-1998 thru CY-2001



ISS PROCESS CONTROL WATER QUALITY MONITOR (PCWQHM) DESIGN & DEVELOPMENT SCHEDULE


ID	Task Name	Duration	Start	1998				1999				2000				2001
				Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	
1	Program Milestones	1d	Thu 1/1/98													
2	Definitize/Start Flight Contract	130d	Thu 1/1/98													
9	Develop/Concur on E.D. w/HSD	47d	Thu 1/1/98													
10	Develop/Concur on S.O.W. w/HSD	47d	Thu 1/1/98													
11	Prep. Proposal based on ED/SOW	30d	Mon 3/9/98													
12	Complete/Ship Proposal	1d	Mon 4/20/98													
13	HSD Review /Evaluate Proposal	15d	Tue 4/21/98													
14	Support Fact Finding by HSD	14d	Tue 5/1/98													
15	Negotiations w/HSD	10d	Mon 6/1/98													
16	Sign Contract	2d	Mon 6/15/98													
17	Formal CSD	1d	Wed 7/1/98													
18	Ramp-Up Manpower (Phase-I)	33d	Thu 1/1/98													
27	Mech. Eng.	33d	Thu 1/1/98													
28	Tech. Writer/Editor-CM/DM	33d	Thu 1/1/98													
29	Contract/SubContract Admin./Buyer	33d	Thu 1/1/98													
30	Product Assurance Eng./Mgr.	33d	Thu 1/1/98													
31	PP&C (Contract)	33d	Thu 1/1/98													
32	Ramp-Up Manpower (Phase-II)	36d	Mon 6/16/98													
33	Elec. Eng. X 2	35d	Mon 6/15/98													
34	Mech. Eng.	35d	Mon 6/15/98													
35	Test Eng	35d	Mon 6/15/98													



Project: PCWQM PROG.: 1998 - 2001
Date: Mon 11/17/97

ISS PROCESS CONTROL WATER QUALITY MONITOR (PCWQM) DESIGN & DEVELOPMENT SCHEDULE

ID	Task Name	Duration	Start	1998				1999				2000				2001			
				Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4
36	Eng./Lab Tech. X 2	35d	Mon 6/15/98																
37	SR&QA Eng.	35d	Mon 6/15/98																
38	Stw. Eng. (Contract)	35d	Mon 6/15/98																
39	Locate, Lease & Prepare Facility	42d	Thu 1/1/98																
47	Locate Lease	8d	Thu 1/1/98																
48	Lease	6d	Tue 1/13/98																
49	Make Pre-Move In Facility Mods	15d	Wed 1/21/98																
60	Move Personnel & Stored Items	24d	Thu 2/12/98																
61	Move Furniture & Fixtures	4d	Thu 2/19/98																
62	Move in Personnel & Setup Offices	1d	Wed 2/18/98																
63	Move Archived PCWQM Documentation	6d	Thu 2/19/98																
64	Move Parts & Materials	7d	Fri 2/27/98																
65	Move Assy & Test Equipment	6d	Tue 3/10/98																
66	Get PCWQM Baseline under CM	77d	Thu 1/1/98																
69	Review archived PCWQM Doc.	11d	Fri 2/27/98																
60	Place latest Rev's in Active Files	12d	Fri 2/27/98																
61	Verify CM baselines	11d	Tue 3/17/98																
62	Update CM baseline, if Req'd	11d	Wed 4/1/98																
63	Update SDD to Agreed Config.	8d	Wed 4/8/98																
64	Setup Labs/Work Areas	82d	Thu 1/1/98																
69	Bonded Stores	6d	Thu 2/19/98																




Project: PCWQM PROG.: 1998 - 2001

Date: Mon 11/17/97

A:\PROJECT4.MPP

ISS PROCESS CONTROL WATER QUALITY MONITOR (PCWQM) DESIGN & DEVELOPMENT SCHEDULE

ID	Task Name	Duration	Start	1998				1999				2000				2001			
				Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4
70	Wet Lab	15d	Tue 3/10/98																
71	Elec. Fab & Assy. Area	28d	Wed 3/18/98																
72	Test Area	6d	Tue 3/10/98																
73	Get Items Back From Boeing	64d	Thu 1/1/98																
74	Coordinate date with Boeing & NASA	11d	Thu 1/1/98																
75	Receive ICSA & PCWQM Docs.	5d	Thu 2/19/98																
76	Receive Parts & Materials	7d	Fri 2/27/98																
77	Receive STE	7d	Fri 2/27/98																
78	SetUp STE	6d	Tue 3/10/98																
79	Complete PCWQM Design Work	261d	Thu 1/1/98																
80	Incorporate Design Mods	174d	Thu 1/1/98																
81	Update Drawings & Part Lists	174d	Thu 1/1/98																
82	Other Deliverable Design Doc's.	174d	Thu 1/1/98																
83	Update Test Procedures	67d	Mon 6/1/98																
84	Update Mfg. Plans & Procedures	22d	Mon 8/3/98																
85	Critical Design Review (CDR)	88d	Tue 9/1/98																
86	Prepare For CDR	14d	Tue 9/1/98																
87	Support CDR	5d	Mon 9/21/98																
88	Resolve CDR RIDS	69d	Mon 9/28/98																
89	Procure Long Lead Items	261d	Mon 3/2/98																
90	EEE Parts	261d	Mon 3/2/98																



ISS PROCESS CONTROL WATER QUALITY MONITOR (PCWQM) DESIGN & DEVELOPMENT SCHEDULE


ID	Task Name	Duration	Start	1998				1999				2000				2001			
				Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	
91	Blue LED's	261d	Mon 3/2/98	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]		
92	Red LED's	261d	Mon 3/2/98	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]		
93	Photodetectors	261d	Mon 3/2/98	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]		
94	IR Sources	261d	Mon 3/2/98	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]		
95	Elec. Connectors	261d	Mon 3/2/98	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]		
96	Wire	261d	Mon 3/2/98	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]		
97	I.C.'s	261d	Mon 3/2/98	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]		
98	Resistors & Capacitors	261d	Mon 3/2/98	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]		
99	Subcontract Items	261d	Mon 3/2/98	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]		
100	Quick Disconnects	261d	Mon 3/2/98	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]		
101	AC Synchronous Motors	261d	Mon 3/2/98	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]		
102	Stepper Motors	261d	Mon 3/2/98	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]		
103	pH Probes	261d	Mon 3/2/98	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]		
104	Valves	261d	Mon 3/2/98	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]		
105	2-Way	261d	Mon 3/2/98	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]		
106	3-Way	261d	Mon 3/2/98	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]		
107	Regulators	261d	Mon 3/2/98	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]		
108	Flow Restrictors	261d	Mon 3/2/98	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]		
109	Pressure Transducers	261d	Mon 3/2/98	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]		
110	Pumps	261d	Mon 3/2/98	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]		
111	Optics	261d	Mon 3/2/98	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]	[]		



Project: PCWQM PROG ; 1998 - 2001
Date: Mon 11/17/97

ISS PROCESS CONTROL WATER QUALITY MONITOR (PCWQM) DESIGN & DEVELOPMENT SCHEDULE


ID	Task Name	Duration	Start	1998				1999				2000				2001
				Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	
112	Beam Splitters	281d	Mon 3/2/98													
113	Stepped Windows	281d	Mon 3/2/98													
114	Convex Lenses	281d	Mon 3/2/98													
115	Build, Assemble, Test & Del. PCWQM	729d	Tue 9/1/98													
116	Finalize Mfg. Plans & Procedures	88d	Tue 9/1/98													
117	Procure Std. Parts & Materials	179d	Thu 10/1/98													
118	Materials for Fab	107d	Thu 10/1/98													
119	Subassembly Parts & Mat'l's	108d	Thu 10/1/98													
120	PCB's	108d	Thu 10/1/98													
121	Mech. Fab. Parts	108d	Thu 10/1/98													
122	Fasteners	108d	Thu 10/1/98													
123	Top Assembly Parts & Mat'l's	113d	Fri 11/1/98													
124	PCB's	113d	Fri 11/1/98													
125	Mech. Fab. Parts	113d	Fri 11/1/98													
126	Fasteners	113d	Fri 11/1/98													
127	Fabricate Parts	92d	Mon 2/1/99													
128	Assemble Subassemblies	90d	Wed 6/9/99													
129	Test Subassemblies	60d	Wed 10/13/99													
130	Assemble Top Assembly	45d	Wed 1/5/00													
131	Test Top assembly	333d	Wed 3/8/00													
132	Charact. & Calibration	60d	Wed 3/8/00													



Project: PCWQM PROG.: 1998 - 2001
Date: Mon 11/17/97

ISS PROCESS CONTROL WATER QUALITY MONITOR (PCWQM) DESIGN & DEVELOPMENT SCHEDULE

ID	Task Name	Duration	Start	1998				1999				2000				2001			
				Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4
133	Functional Testing	60d	Wed 5/31/00																
134	Pre-Environmental Qual Testing	60d	Wed 8/23/00																
136	Environmental Qual Testing	90d	Wed 11/15/00																
136	Post Environmental Qual Testing	20d	Wed 3/21/01																
137	Final ATP	43d	Wed 4/18/01																
138	Compile PCWQM & STE ADP for Ship	10d	Tue 6/12/01																
139	Pack & Ship PCWQM, ADP & STE	8d	Wed 6/20/01																
140	Contract Closeout	66d	Fri 6/29/01																
141																			
142	Major Milestones	977d	Thu 1/1/98																
143	Start Ramp Up	1d	Thu 1/1/98	1/1															
144	Start Long Lead Item Procurements	1d	Mon 3/29/98		◆ 3/2														
145	Critical Design Review	1d	Mon 9/21/98			◆ 9/21													
146	Start Part Fab	1d	Mon 2/1/99				◆ 2/1												
147	Start Subassembly build	1d	Tue 6/8/99					◆ 6/8											
148	Start PCWQM Calibration	1d	Tue 3/7/00						◆ 3/7										
149	Start PCWQM Funct. Testing	1d	Tue 5/30/00							◆ 5/30									
150	Start Pre-Environmental Qual Testing	1d	Tue 8/22/00								◆ 8/22								
151	Start Environmental Qual Testing	1d	Tue 8/22/00									◆ 8/22							
162	Start Final ATP	1d	Wed 4/18/01										◆ 4/18						
163	Start FCA/PCA	1d	Fri 6/15/01											◆ 6/15					



Project: PCWQM PROG.: 1998 - 2001
Date: Mon 11/17/97

Progress
Milestone

A:\PROJECT4.MPP

Page 6

Mon 11/17/97 7:31 PM

ISS PROCESS CONTROL WATER QUALITY MONITOR (PCWQM) DESIGN & DEVELOPMENT SCHEDULE

ID	Task Name	Duration	Start	1998				1999				2000				2001			
				Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	
164	Ship Hardware & ADP's	1d	Fri 6/29/01															◆ 6/29	
166	Contract Closeout Complete	1d	Fri 8/28/01															▼	

Project: PCWQM PROG.: 1998 - 2001 Date: Mon 11/17/97	Task Progress Milestone	Summary	Rolled Up Progress
		◀	▶
		Rolled Up Task ◆	
		Rolled Up Milestone ◇	

A:\PROJECT4\mpp

Mon 11/17/97 7:31 PM

Page 7

PCWQM PROGRAM ISSUES/COST DRIVERS

What is to be delivered ?

Flight Units

Protoflight Units

Qual Units

Special Test Equipment

Spares

What requirements are to be imposed?

Space Station Full Flight, Crit 1R

Space Station Protoflight

NASA Flight Experiment

PCWQM PROGRAM ISSUES/COST DRIVERS

What is the desired delivery date/(s) ?

ASAP

Best date based on overall program cost, but not later
than ____

Driven by availability of funds

**What programmatic requirements must be
flowed down to subcontractors ?**

Full

Partial

None

PCWQM PROGRAM ISSUES/COST DRIVERS

Will DCMO be required to perform source inspection/acceptance at subcontractor facilities?

Yes

No

To what extent will HSD QA & DCMO be involved in our assembly and test activities?

Heavily

Minimally

PCWQM PROGRAM ISSUES/COST DRIVERS

Will Zellweger be given MRB authority?

Yes

No

Will NASA facilities be available to support environmental testing ? Can they be used?

JSC

MSFC

PCWQM PROGRAM ISSUES/COST DRIVERS

What EEE Part Requirements are to be imposed?

Class - "S"

MIL-883B

Best Commercial Grade

Will a detail-level Finite Element Analysis be required?

Full FEA required

Tailor based on areas of concern

Not required

PCWOM PROGRAM ISSUES/COST DRIVERS

What program reviews are to be conducted?

Delta - CDR

FCA/PCA

AR

What will the program status reporting requirements be?

Monthly cost, schedule and performance

Variance analysis, recovery plans, etc.

SDB Subcontracting

PCWQM PROGRAM ROM COST ESTIMATE

Direct Labor Hours	76752
Total Labor Cost	\$1,967,282
Overhead @ 119%	\$2,341,066
Direct Material	\$176,876
Direct Subcontract	\$1,378,987
Direct Contract Labor	\$210,000
Direct Freight	\$16,429
Direct Travel	\$63,360
Other Direct Costs	\$36,000
Total Direct Cost	\$6,190,000
G&A @ 25.7%	\$1,590,830
Total Cost	\$7,780,829
Fixed Fee	\$389,041
Total	\$8,169,871

1. 36 Month Program
2. Average H.C = 12.4
3. One PCWQM delivered to Space Station Prototype Requirements
4. Approx. \$227K/mo. Funding Req'd.

PRICING FOR ION STAGE-11 PCWQM REQUEST FOR PROPOSAL

SOW PARA	SOW TASK DESCRIPTION										PPAC	
	ES	ED	S. Eng.	Technician	MGR	STC	ENG	EEC. Eng.	Total HRS	Material Cost	SM. Eng.	Tareel Cost
A Evaluate & Definitive Program Requirements	200	160										
B Identify>Select Valve Suppliers	70	70										
C Conduct Packaging Analysis	80	120										
D Mod. CO2 Detector Source	80	120										
E Identity>Select Supplier for UV Power Supply	40	20										
F Identity>Select Suppliers for Other Long-Lead Key Components												
AC Synchronous Motors	40	40										
Slepper Motors	40	40										
pH Probes	40	40										
Regulators	40	40										
Optics	40	40										
Pumps	40	80										
Flow Restrictors	40	40										
Pressure Transducers	60	80										
IR Sources	40	40										
Blue LED's	40	20										
Red LED's	40	20										
Photodetectors	40	20										
G Identity>Select Supplier for Firmware Controller Components	70	140										
H Identity and Coordinate Transfer of Items from ICSA Program	160	80										
I Modify Dng's and Associated Part Lists to Reflect Changes	160	160										
Package RelistedUpgraded Stage-11 PCWQM Unit for Ship Final Report	20	30										
	60	40										
TOTAL LABOR HRS.	1440	1440	200	522	342	603	1440	6187	\$178,174	290	450	
TOTAL LABOR \$\$	\$52,013	\$52,013	\$3,966	\$11,437	\$7,493	\$10,257	\$31,210	\$3,786	\$178,174	\$7,521	\$14,500	\$15,750
MAN Wk's EQUIV	36.0	36.0	5.0	13.1	8.6	15.1	36.0	5.0	154.7	7.3	11.3	
MAN MCR EQUIV	9.0	9.0	1.3	3.3	2.1	3.8	9.0	1.3	38.7	1.8	2.8	
MAN TRNs EQUIV	0.7	0.7	0.1	0.3	0.2	0.3	0.7	0.1	3.0	0.1	0.2	
AVG/Mo. Assuming 9 Mo Project	1.0	1.0	0.1	0.4	0.2	0.4	1.0	0.1	4.30	0.2	0.3	
MGR	2880	\$102,038.40										
SNR	1440	\$17,299.60										
ENG	864	\$18,930.24										
SPL	0	90.00										
DFT	603	\$10,257.03										
STC	200	\$3,966.00										
MCH	200	\$3,786.00										
TOTAL	6187	\$178,174										
TOTAL												\$564,000

ASSUMPTIONS RELATED TO PCWQM PROGRAM ROM COST ESTIMATE

- 1 Design Baseline is PCWQM-SEU Multiple ORU Configuration as submitted to Boeing in March 1995
- 2 Space Allocation for the PCWQM is same as for the PCWQM-SEU, plus an additional 6" in depth for Power Supply and Firmware Controller.
- 3 ICSA Pre-Production and ProtoFlight Units will be returned from Boeing to facilitate the ProtoFlight Iodine and Conductivity Sensors being used in the PCWQM.
- 4 PCWQM/ICSA STE will be returned from Boeing to support testing.
- 5 All PCWQM and/or ICSA Program residual equipment, hardware and spare parts will be returned from Boeing for use on this program.
- 6 All PCWQM and/or ICSA Program documentation and data will be returned from Boeing for use on this program.

ASSUMPTIONS RELATED TO PCWQM PROGRAM ROM COST ESTIMATE

- 7 Incremental EEE Part Lists and EEE Parts Applications Analysis reports will not be required. EEE Parts Lists and related analyses updates will be submitted as they are completed.
- 8 Full Environmental Qual (Prototypal-Levels) and ATP will be performed on Top Assembly
- 9 A detailed part-level Finite Element Analysis will not be required. Thermal and structural analyses will be limited to specific areas of concern.
- 10 Detailed incremental Mass Properties Reports will not be required. Estimates and actuals will be submitted as appropriate.
- 11 Software code will be written and delivered in C + +
- 12 Individual valves will not require position indicators.

ASSUMPTIONS RELATED TO PCWQM PROGRAM ROM COST ESTIMATE

- 13 FDI will be limited to only that which is necessary to isolate a problem to the ORU-level.
- 14 Drawings, parts lists and other deliverable documents can be delivered on electronic media using industry standard formats.
- 15 On-orbit maintenance will be limited to ORU removal and replacement.
- 16 A delta-CDR will be held approx. 12 months after CSD.
- 17 This will be approx. a 36 month program, assuming it starts in July 1998, following a planned six-month build-up and requirements definition period. (Duration heavily dictated by procured item lead times and test durations)
- 18 Solid Phase Acidifier ORU can be replaced after 2000 hrs. (Approx. 3 mo.) of operation.

ASSUMPTIONS RELATED TO PCWQM PROGRAM ROM COST ESTIMATE

- 19 pH Probe ORU can be replaced after 8760 hours (approx. 12 mo.) of operation.
Note: Strong possibility exists that this life limit can be extended appreciably (i.e., to 36 mo.) thru testing.
- 20 All PCWQM external interfaces (mechanical/structural, electrical, thermal, fluid) are clearly defined and agreed upon at a very early stage of the program.
- 21 Program Planning, Scheduling, and Control requirements will not dictate a full time PP&C Specialist.
- 22 Full Environmental Qual (Prototypal-Levels) and ATP will be performed on Top Assembly

PCWQM Program Technical History

- Boeing decided in 1991 to eliminate UV Ballast Supply, DC/DC Power Supplies, Firmware Controller, Turbidity Sensor, and Class S EEE parts from contract as a cost reduction.
- Boeing was to provide Class S EEE parts and handle integration of Astro's PCWQM-SEU to Boeing's FWC, UV Supply, DC Power Supply, and PCWQM software 3 years after PCWQM-SEU delivery.
- PCWQM-SEU presented at CDR was "single ORU" although a T1M took place in April '93 discussing multiple ORU configuration - Boeing didn't want to change baseline for CDR.

PCWQM Program Technical History

- 154 RIDs issued at CDR, one of which used to justify design change to Multiple ORU PCWQM-SEU.
- “Least number of RIDs issued to any Space Station subcontractor” . . . All closed by start of ICSA build.
- Based upon the development testing status at the time, Multiple ORU configuration became defined as follows . . .

PCWQM ORU's MANIFOLD ASSEMBLIES

ORU Number	Orbital Replacement Unit (ORU) Description
1	PCWQM Top Assembly, Less ORU - 2 and ORU - 3 (3 to 5 Year Life)
2	Heated Solid Phase Acidifier (SPA) Module (90 Day Life @ 42% Duty Cycle)
3	SPA #2, pH Assembly, and Valves (>1 Year Life)

Manifold Number	Manifold Description
1	ORU Interface Manifold (Connects ORU - 3 to mainframe)
2	ORU - 3 Manifold (Connects ORU - 2 to ORU - 3)
3	ORU - 2 Manifold (Piece Part Detail of ORU - 2)
4	UV Reactor Interface Manifold (Ties to UV Reactor, Cold Plate, & Mounting Plate)
5	Oxygen Manifold (Oxygen Gas Loop)
6	Sample Out Manifold (Ties Waste Out to QD - 4)
7	Recirculation Manifold (Sample Loop Inlet Valve)

ORU_LST.xls ORU_LST

Page 1

11/19/97 8:55 AM

Ezellweger analytics

PCWQM Program & Design Status


November 20, 1997



BOEING

SYSTEM LEVEL DESIGN

PCWQM-SEU BLOCK DIAGRAM






BOEING

SYSTEM LEVEL DESIGN



PCWQM-SEU FLOW DIAGRAM



BOEING

SYSTEM LEVEL DESIGN

PCWQM-SEU TOP VIEW






BOEING

SYSTEM LEVEL DESIGN

PCWQM-SEU BOTTOM VIEW






BOEING

SYSTEM LEVEL DESIGN

MECHANICAL INTERFACES



FRONT VIEW

DWG #7330036, REV. D


3.4.1.1



BOEING

ELECTRICAL INTERFACES

ELECTRICAL INTERCONNECT PCWQM-SEU ORU ELECTRICAL INTERFACE



DWG #7330035, REV. C




BOEING

ELECTRICAL INTERFACES

ELECTRICAL INTERCONNECT ELECTRICAL POWER CONNECTOR

Boeing ← → Astro



INTC00-1SH19

19 •20 contact

INTC00-1SH19P

Power Connector 1/F

NOTE:

1. Pin #1 in Power Connector are unconnected
2. All pins utilized o connection will be installed

DWG #7330035, REV. C

3.4.2.1




ELECTRICAL INTERFACES

ELECTRICAL INTERCONNECT PCWQM-SEU BUS INTERFACE

BOEING

BOEING → ASTRO
FMC & CABLE I/F
PCWQM





ELECTRICAL INTERFACES

DWG #7330035, REV. C

ELECTRICAL INTERCONNECT SIGNAL CONNECTOR INTERFACE

Rowing → → Asmro

Inst Ref Designated On Part	P2	J2	
1	1	I2P_MUX_Addrl.	A00.
2	2	I2P_MUX_Addrl2.	A01.
3	3	I2P_MUX_Addrl2.	A01.
4	4	I2P_MUX_Addrl2.	A01.
5	5	I2P_MUX_Addrl2.	A02.
6	6	I2P_MUX_Addrl2.	A02.
7	7	Sens_MUX_Addrl.	A03.
8	8	Sens_MUX_Addrl2.	A03.
9	9	Sens_MUX_Addrl2.	A04.
10	10	Sens_MUX_Addrl2.	A04.
11	11	Sens_MUX_Addrl2.	A05.
12	12	Sens_MUX_Addrl2.	A05.
13	13	Control[1].	A06.
14	14	Control[1].	A06.
15	15	Control[2].	A07.
16	16	Control[2].	A07.
17	17	Control[2].	A08.
18	18	Control[2].	A08.
19	19	ADC_Select.	A09.
20	20	ADC_Select.	A09.
21	21	ADC_Read.	A10.
22	22	ADC_Read.	A10.
23	23	NVRAM_Enable.	A11.
24	24	NVRAM_Enable.	A11.
25	25	Space_Addrl.	A12.
26	26	Space_Addrl.	A12.
27	27	Space_Addrl2.	A13.
28	28	Space_Addrl2.	A13.
29	29	Space_Addrl2.	A14.
30	30	Space_Addrl2.	A14.
31	31	Space_Addrl2.	A15.
32	32	Space_Addrl2.	A15.
33	33	Datal00[LSB].	D00.
34	34	Datal00[LSB].	D00.
35	35	Datal00[LSB].	D01.
36	36	Datal00[LSB].	D01.
37	37	Datal00[LSB].	D02.
38	38	Datal00[LSB].	D02.
39	39	Datal00[LSB].	D03.
40	40	Datal00[LSB].	D03.

1	41	BData104.	D04.
2	42	BData104.	D04.
3	43	BData105.	D05.
4	44	BData105.	D05.
5	45	BData106.	D06.
6	46	BData106.	D06.
7	47	BData107.	D07.
8	48	BData107.	D07.
9	49	BData108.	D08.
10	50	BData108.	D08.
11	51	BData109.	D09.
12	52	BData109.	D09.
13	53	BData110.	D10.
14	54	BData111.	D10.
15	55	BData111.	D11.
16	56	BData111.	D11.
17	57	BData112.	D12.
18	58	BData112.	D12.
19	59	BData113.	D13.
20	60	BData113.	D13.
21	61	BData114.	D14.
22	62	BData114.	D14.
23	63	BData115[MSB].	D15.
24	64	BData115[MSB].	D15.
25	65	TBD (Space).	TBD (Space)
26	66	Signal.Gnd.	SG
27	67	Signal.Gnd.	SG
28	68	Signal.Gnd.	SG
29	69	Signal.Gnd.	SG
30	70	Signal.Gnd.	SG
31	71	TBD (Space).	TBD (Space)
32	72	TBD (Space).	TBD (Space)
33	73	TBD (Space).	TBD (Space)
34	74	TBD (Space).	TBD (Space)
35	75	TBD (Space).	TBD (Space)
36	76	TBD (Space).	TBD (Space)
37	77	TBD (Space).	TBD (Space)
38	78	TBD (Space).	TBD (Space)
39	79	TBD (Space).	TBD (Space)

NA1C0_2IN35S
79-220 contacts

NA1C06621IN35SN

NA1C00121IN35PN

BOEING


ASTRO-BOEING PCWQM-SLJ CRITICAL DESIGN REVIEW
NOVEMBER 1993



BOEING

ELECTRICAL INTERFACES

ELECTRICAL INTERCONNECT TIMING DIAGRAM & SOFTWARE INTERFACE



DWG #7330035, REV. C

3.4.2.4



BOEING

SYSTEM LEVEL DESIGN

DEVELOPMENT TESTING COMPLIANCE

UNIT	REQUIRED/DERIVED ACCURACY	TEST TYPE	MEASURED ACCURACY TO DATE	SCHEDULED TEST DATE DOCUMENT NUMBER
pH	± 0.5	Formal	< ± 0.36 pH	Complete, see AIC-SS-1202
MOTOR PUMP	± 0.01 ml/min (derived)	Formal	± 0.01 ml/min	Complete, see AIC-SS-1167
1/4 INCH TEMPERATURE	± 1.0 °F	Formal	± 0.36 °F	Complete, see AIC-SS-1220
1/4 INCH CONDUCTIVITY	± 1.0 μ S/cm	Formal	± 0.25 μ S/cm	Complete, see AIC-SS-1220
IODINE	± 0.2 mg/l	Formal	± 0.10 mg/l	Complete, see AIC-SS-1253
CO ₂ DEFLECTOR	± 10 ppm CO ₂ (derived)	Formal	± 8 ppm CO ₂	In process, see AIC-SS-1258
UV REACTOR	Oxidation ≥ 90% with a < 2 mg C/l sample (derived)	Formal	95%	In process, see AIC-SS-1258
TIC/GLS	Residual < 30 μ g/l with a 5 mg C/l sample (derived)	Formal	< 20 μ g/l	In process, see AIC-SS-1258
0.04 INCH TEMPERATURE	± 2.5 °F (derived)	Formal	0.36 °F by similarity	Complete, see AIC-SS-1220
0.04 INCH CONDUCTIVITY	± 10.0 μ S/cm (derived)	Formal	< ± 7.9 μ S/cm	Complete, see AIC-SS-1241
HIGH CALIBRATION MODULE	± 0.1 pH units over operational life	Formal	± 0.25 pH units over operational life	Complete, see AIC-SS-1265
LOW CALIBRATION MODULE	± 0.1 pH units over operational life	Formal	± 0.1 pH units over operational life	Complete, see AIC-SS-1265
SOLID PHASE ACIDIFIER	pH < 4.0 for 2,880 hours (211.1 liters)	Formal	> 25 liters	In process, see AIC-SS-1284
TOCV MODULE	± 50 μ g C/l over operational life	Formal		December 1993



PROCESS LOOP TEMP./CONDUCTIVITY SENSOR

REQUIREMENTS

The process loop temperature/conductivity sensor design results in the following derived functional requirements:

- Conductivity measuring range = $1 - 30 \mu\text{S}/\text{cm}$ compensated to 25°C using standard solution SRM 3190 as a reference
- Conductivity sensitivity/tolerance = $\pm 1.0 \mu\text{S}/\text{cm}$
- Temperature measuring range = $50 - 150^\circ\text{F}$
- Temperature sensitivity/tolerance = $\pm 1.0^\circ\text{F}$ ($\pm 0.56^\circ\text{C}$)
- Operating flow rate = $15 - 17 \text{ lb/hr}$ ($100-130 \text{ ml/min}$)
- Supplied water shall be gas free


BOEING



PROCESS LOOP TEMP./CONDUCTIVITY SENSOR

DESIGN

BOEING





BOEING

IODINE DETECTOR

REQUIREMENTS

The PCWQM-SEU requires iodine measurement with the following specifications:

- Iodine measuring range = 0.1 - 6.0 mg/l
- Iodine sensitivity/tolerance = ± 0.2 mg/l at iodine-iodide equilibrium in pure water and constant pH for accuracy during process
- Operating temperature range = 50 - 150 °F
- Operating flow rate = 15 - 17 lb/hr (100-130 ml/min)
- Supplied water shall be gas free
- Operating pH range = 5 - 9 pH units



BOEING

IODINE DETECTOR

REQUIREMENTS

The iodine detector design results in the following derived functional requirements:


- Optical path length ≤ 18 cm



BOEING

IODINE DETECTOR

IODINE DETECTOR BLOCK DIAGRAM





BQEING

PH MEASURING SUBSYSTEM

REQUIREMENTS

The PCWQM-SEU requires pH measurement with the following specifications:

- pH measuring range = 5 - 9 pH units
- pH sensitivity/tolerance = ± 0.5 pH units
- Operating temperature range = 50 - 150 °F

The pH sensor design results in the following derived functional requirements:


- Operating flow rate = 1 - 5 ml/min




BOEING

pH SENSOR

DESIGN





SOLID PHASE CALIBRATION STANDARDS

REQUIREMENTS - SOLID PHASE PRECONDITIONER

The Solid Phase Preconditioner (SPP) design results in the following derived nominal operating requirements:

- Flow rate = 1 ml/min
- Conductivity range = 1 - 30 $\mu\text{S}/\text{cm}$
- pH range = 5 - 9 pH units
- TOC range = 50 - 1000 $\mu\text{g/l}$
- Iodine range = 0.1 - 6.0 mg/l
- Temperature range = 50 - 150 °F
- TIC range = 0 - 5 mg/l


 ASTRO-BOEING PCWQN. CRITICAL DESIGN REVIEW
NOVEMBER 1993

SOLID PHASE CALIBRATION STANDARDS

REQUIREMENTS - LOW SOLID PHASE CALIBRATION STANDARD

The Low Solid Phase Calibration Standards design results in the following derived functional requirements:


- Preceded by a Solid Phase Preconditioner (SPP)
- Effluent pH range = 3 - 5 pH units
- pH stability over operational life = ± 0.1 pH units
- Operational life span = 300 20 minute cycles



ASTRO-BOEING PCWQM-1
CRITICAL DESIGN REVIEW
NOVEMBER 1993

SOLID PHASE CALIBRATION STANDARDS

DESIGN



Solid Phase Material



BOEING

TOC MEASURING SYSTEM

REQUIREMENTS

The PCWQM-SEU requires TOC measurement with the following specifications:

- Measuring range = 100-1000 $\mu\text{g/l}$
- Sensitivity/tolerance = \pm 50 ppb



BOEING

SOLID PHASE ACIDIFIER

REQUIREMENTS

The solid phase acidifier design results in the following derived functional requirements:

- Effluent < 4.0 pH units
- TOC contribution < 10 $\mu\text{g C/l}$
- Operational life span = 2880 hours (Equivalent to 211.2 liters throughput)



SOLID PHASE ACIDIFIER

BOEING

REQUIREMENTS

The solid phase acidifier design results in the following derived nominal operating requirements:

- Flow rate = 1 and 5 ml/min
- Conductivity range = 1 - 120 $\mu\text{S}/\text{cm}$
- pH range = 3 - 10.5 pH units
- TOC range = 50 - 1000 $\mu\text{g/l}$
- Iodine range = 0.1 - 6.0 mg/l
- Temperature range = 50 - 150 °F
- TIC range = 0 - 5 mg/l



TIC GAS/LIQUID SEPARATOR

REQUIREMENTS

The Total Inorganic Carbon/Gas Liquid Separator (TIC/GLS) design results in the following derived requirements:

- TIC residual < 30 $\mu\text{g C/l}$ at a TIC influent \leq 5 mg C/l
- TIC operating range = 0 - 5 mg C/l
- Provide oxygenation greater than 20 mg O₂/l at 1 atmosphere
- Influent pH < 4.0 pH units
- Operational flow rate = 1 ml/min
- Operating temperature range = 50 - 150 °F
- Operational performance insensitive to orientation (simulated zero G)
- O₂ influent flow rate = 20-50 sccm

BOEING




BOEING

UV REACTOR

REQUIREMENTS

The UV reactor design results in the following derived requirements:

- Oxidation $\geq 90\%$ with TOC sample of urea $\leq 1.5 \text{ mg C/l}$
- Operational influent pH < 4.0 pH units
- Operational flow rate = 1 ml/min
- Operating temperature range = 50 - 150 °F



BOEING

UV BALLAST

REQUIREMENTS

- UV REACTOR STEPUP, HIGH VOLTAGE OUTPUT TRANSFORMER
 - Envelope and mechanical interface defined in SK683-20929 of April 9, 1993
 - Two primary coils rated for 100 volts max.
 - Two secondary coils rated for 4000 volts max (40:1 turns ratio each)
 - Encapsulated; Electrical terminals are MIL-T-55155/15C
 - Qualified to MIL-STD-981 Class S consistent with MIL-STD-975J
- * Specifications are to change per October 27, 1993 UV Ballast PDR
Telecon



BOEING

CARBON DIOXIDE DETECTOR

REQUIREMENTS


The CO₂ detector design results in the following derived operating requirements:

- Temperature range = 50-104 °F
- Flow rate = 1 ml/min ± 0.01 ml/min
- Inlet sample pH ≤ 4
- Inlet TIC residual ≤ 30 µg C/l
- 90% of sample TOC in the form of CO₂ (minimum)
- CO₂ detector cell surface ≥ 1 °C above inlet temperature of sample
- O₂ flow rate = 0-275 sccm



COMPONENT LEVEL DESIGN

SYSTEM OVERVIEW





BOEING

Mounting Plate Assembly

Requirements

- Change in front panel attachment points from center plane to top of front panel from ICD resulted in redesign. Requires more rigid (heavier) front panel due to cantilevered mounting of front panel.
- Front panel shall meet human factors of NASA-STD-3000 for rounded corners, connector spacing, attachment points
- Mounting plate assembly shall be self aligning, require no complex actions, unable to be installed in the wrong orientation
- Support PCWQM-SEU component assemblies during launch vibration, acceleration, and crew induced loads
- 1-g installation/removal force shall be less than 35 lbs
- Provide conduction path for heat rejection from components to integral heat exchanger
- Fasteners removable on orbit must be captive


ASTRO-BEING PCWQM-SEU CRITICAL DESIGN REVIEW
NOVEMBER 1993



BOEING

Mounting Plate Assembly

Design




ASTRO-BEING PCWQM-SEU CRITICAL DESIGN REVIEW
NOVEMBER 1993



BOEING

Mounting Plate Assembly

Design





BOEING

MOTOR/PUMP AND CONTROLLER

REQUIREMENTS

The motor/pump design results in the following derived requirements:

- Flow rate = 1 and 5 ml/min
- Pressure rise = 10 -25 psig
- Flow stability = ± 0.01 ml/min @ 1 ml/min
- Flow stability = ± 0.25 ml/min @ 5 ml/min



BOEING

SAMPLE MANIFOLDS

REQUIREMENTS


- Minimize the requirement for tubing runs by grouping components onto manifolds
- Reduce the risk of leakage by mounting interconnected components on opposite sides of the manifold and by using drilled holes
- Reduce sensitivity to variation on multi-port components by using static face seals against the manifold
- Minimize manifold size and weight
- Locate heat generating components as close as possible to the avionics air heat sink
- Profile manifolds where required to maintain clearance to other subassemblies



BOEING

SAMPLE MANIFOLD

DESIGN - SAMPLE MANIFOLD 1




ASTRO-BOEING PCWQM-SEU CRITICAL DESIGN REVIEW
NOVEMBER 1993



BOEING

SAMPLE MANIFOLD

DESIGN - SAMPLE MANIFOLD 2






BOEING

SAMPLE MANIFOLD

DESIGN - SAMPLE MANIFOLD 3




ASTRO-BOEING PCWQM-SEU CRITICAL DESIGN REVIEW
NOVEMBER 1993



BOEING

SAMPLE MANIFOLD

DESIGN - SAMPLE MANIFOLD 4





SENSOR/EFFECTOR ADDRESS DECODER

REQUIREMENTS

SEAD ANALOG SIGNAL FUNCTIONAL REQUIREMENTS:

- 32 channels of single ended analog inputs with range of -10 to + 10 volts dc
- Static input voltage accuracy of $\pm 0.003\%$ of Full Scale Range (FSR) at a 1 kHz sampling rate
- Static input voltage resolutionaccuracy of at least $610 \mu\text{V}/\text{Least Significant Bit (LSB)}$
- Dynamic error $< \pm 0.0224\%$ FSR at a signal slew rate of 0.5 volts per second at a 10 kHz sampling rate
- Provide interface to firmware controller via 2 wire/line RS-422 balanced receivers/drivers
- Cabable of receiving or transmitting 16 bit wide data bus signals
- Cabable of storing, semipermanently, minimum $2K \times 8$ bit sensor calibration coefficients



SENSOR/EFFECTOR ADDRESS DECODER

REQUIREMENTS

SEAD DIGITAL SIGNAL FUNCTIONAL REQUIREMENTS:

- 16 Transistor-Transistor Logic (TTL) channels of digital input with the following characteristics:
 - Minimum high level input voltage is $V_{IH} = 2.0$ volts
 - Maximum low level input voltage is $V_{IL} = 0.8$ volts
- 32 channels of digital output with the following characteristics:
 - Minimum high level voltage $V_{OH} = 2.4$ (Min) with an output current of $I_{OH} = -4.0$ mA
 - Maximum low level voltage $V_{OL} = 0.45$ (Max) with an output current of $I_{OL} = 8.0$ mA



BOEING

SENSOR/EFFECTOR ADDRESS DECODER

REQUIREMENTS

SEAD SAMPLE RATE FUNCTIONAL REQUIREMENTS

- Maximum sample rate frequency of 10 kHz
- Sample rate accuracy of \pm 50 Hz
- Sample rate stability of \pm 1% of the setting

SEAD BIDIRECTIONAL DATA BUS COMMUNICATION FUNCTIONAL REQUIREMENTS

- The input command yields the appropriate output effector command 100% of the time



ASTRO-BEING PCWQM-SEU CRITICAL DESIGN REVIEW
NOVEMBER 1993

BOEING

SENSOR/EFFECTOR ADDRESS DECODER

REQUIREMENTS

SEAD VALVE DRIVER CIRCUIT FUNCTIONAL REQUIREMENTS

- Provide PWM drive to valve with 0.14% duty cycle after initial drive of + 28 volts for 50 ms.

SEAD CONDENSATE DETECTOR CIRCUIT FUNCTIONAL REQUIREMENTS



- Convert the condensate detector's analog signal to a 1 bit digital signal



BOEING

SENSOR EFFECTOR ADDRESS DECODER


DESIGN




ICSA Program Design Status

- Boeing directed change from PCWQRM-SEU to ICSA configuration effective March 31, 1995
- Deliverables:
 - 1 Pre-Production prototype Unit [PPU]: A) work out any layout bugs; B) built w/Class B EEE parts or parts from Class S lot being tested; C) verify calibration and test procedures; D) Boeing planned to ultimately deliver to Hamilton Standard to assist in WP integration.
 - 1 Protosflight Unit [PFU]: A) supposed to be 100% Class S EEE parts; B) reduced Qual Test levels; C) intended to be used for Flight.
 - STE: Automated test system designed for calibrating and performing ATP for PCWQRM and ICSA.


ICSA Flow Diagram





LEGEND:





ICSA Mechanical Interface Components




Iodine-Conductivity Sensor Assembly




ISOMETRIC VIEW
REVERSE ON THE IN GATE




ICSA Mechanical Interface Dimensions



Iodine Detector





Temperature/Conductivity Sensor – Process Loop

ICSA Program Design Status

- Open Issues/Status:
 - PPU meet objectives stated above. ∴ no issues (Not for Flight!)
 - Boeing directed ZALC to complete build of PFU with some non-Class S EEE parts (upscreened DESC parts; red LED; AD590 temp sensor)
 - Calibration was performed as required
 - ATPs were modified to reduce Schedule: no thermal cycling; limited full range temperature sensor performance verifications; no Vibe; no EMI; no pressure or vacuum.
 - Boeing's plan was to take PFU apart, install correct Class S parts, re-calibrate, execute PFU Qual ATP using STE

ICSA Program Design Status

ICSA Design considered a success that exceeded performance requirements (60 hour ATP):

- “Temperature sensitivity/tolerance of $\pm 1.0^{\circ}\text{F}$ over range of 50 to 150°F ”

ATP data: $\pm 0.12^{\circ}\text{F}$ { $\pm 0.61^{\circ}\text{F}$ (3 σ)}

- “Conductivity sensitivity/tolerance of $\pm 1.0 \mu\text{S}/\text{cm}$ over range of 1 to $30 \mu\text{S}/\text{cm}$ compensated to 25°C using SRM 3190 as reference standard”

ATP data: $\pm 0.12 \mu\text{S}/\text{cm}$ { ± 0.88 (2 σ)}

ICSA Program Design Status

- “Iodine Sensor sensitivity/tolerance of ± 0.2 ppm over range of 0.1 to 6.0 mg I₂/L at iodine-iodide equilibrium in WP H₂O and constant pH”
 - ATP data: ± 0.11 mg I₂/L over range (1 σ)
- All ICSA hardware & documentation and PCWQM-SEU documentation shipped to Boeing April 25, 1997
- ZALC assumes current plan is to recover PPU & PFU ICSAs for use within PCWQM where appropriate
- ZALC also assumes STE will be recovered for use by PCWQM Program

1997 PCWQM Program Development

- ION Associates funded further development work towards PCWQM under “lessons learned” from Stage 10.
- Conclusions of Studies done for ION:
 - ZALC-SS-1601: GLS membrane material *is* available from alternative vendors
 - ZALC-SS-1600: “membrane failures” were not failures of membrane material: 2 caused by spacing shims (subsequent design has eliminated them); 1 caused by defective o-ring (subsequent assembly procedures call for microscopic inspection prior to incorporation into unit)

1997 PCWQM Program Development

- Conclusions of Studies done for ION (continued):
 - ZALC-SS-1602: Recommend further life testing to justify >1 yr life for ISFET probe (ORU3); or could replenish electrode gel on-orbit
 - ZALC-SS-1603: baslined Honeywell (nee Leeds & Northup) pH probe still available and no problems in future procurement expected; alternative vendors available, but design impacted.
 - ZALC-SS-1606: UV Ballast power supply subcontractors do exist and could cost effectively design/manufacture to Class B type requirements.

1997 PCWQM Program Development

- Conclusions of Studies done for ION (continued):
 - ZALC-SS-1607: Suggest incorporation of 254 nm solid state detector into UV Lamp Assembly to monitor intensity.
 - ZALC-SS-1608: TOC measurement range extension to 5000 ppb TOC can happen with virtually no impact if accuracy requirement set to $\pm 5\%$ of reading over 1 to 5 ppm range.
 - ZALC-SS-1605: Modeling and packaging study drawings follow, with recommendation that PCWQM incorporate power supplies and firmware controller for a true “turn key” instrument eliminating complex integration.


PCWQM Program Technical History

- PCWQM-SEU is a “dumb” assembly relying on external command and control of effectors and sensors.
- Baseline design results in two (2) large connectors:
 - J1 = Power: +5, +28, ± 15 and associated returns
 - J2 = Signal: 32 twisted, shielded pairs
- Boeing to provide cabling up to PCWQM-SEU front panel . . . significant weight
- PCWQM Integration Nightmare:
 - PCWQM-SEU to External DC Power supplies
 - PCWQM-SEU to third party External FWC
 - PCWQM-SEU to third party software


1997 PCWQM Program Development


- Advantages of “self contained” PCWQM:
 - Improves significantly likelihood of successful higher level integration
 - Significantly reduces testing problems
 - Instrument provides a serial data stream (re: Stage 9 and Stage 10 PCWQM) with data already converted to scientific values (calculations already performed, PCWQM state and FDI status provided, overrides available, etc.)
 - Weight delta negligible: compare FWC weight -vs- 32 twisted pairs w/shields, connectors, multiple power lines, etc.

PCWQM Flow Diagram (7330168-00 Rev G)



LEGEND







Two Step Down Power Distribution Approach

POWER SYSTEM DESIGN

Single Step Down Power Distribution Approach
POWEREST.xls, Scenario #2



Electrical Interconnect Diagram (7330074-00 Rev D)



November 20, 1997


PCWQM Program & Design Status

zellweger analytics


Description:	Ref. Des.	Locale	Channel Count (wrt SEAD)		
			Digital Out	Digital In	Analog In
Conductivity	TC1, C	B7	0.5		1
Iodine	ID1	B7	1	2	2
Motor, Metering	PM1	B5	2		
Motor, TOC Stepper	IG1, M	C4	1	1	
pH sensor	PH1	C7	1		1
Pressure Xdcr	PT1-1	C7			1
Pressure Xdcr	PT1-2	B5			1
Pressure Xdcr	PT2-2	D3			1
Pressure Xdcr	PT2-4	B6			1
Pressure Xdcr	PT3-1	B4			1
Pressure Xdcr	PT3-2	C4			1
Pressure Xdcr	PT3-3	C5			1
Pressure Xdcr	PT4-2	C6			1
Temperature	TC1, T	B7	0.5		1
Temperature	TT1-1	C4			1
Temperature	TT1-2	C4			1
Temperature	TT1-3	C5			1
Temperature	TT1-4	C5			1
Temperature	TT1-5	C6			1
Temperature	TT1-6	C4			1
TOC (CO2 Detector)	IG1	C3	1		1
SPA Heater	HT1	C7	1		
IR/GLS Heater	HT2	C4	1		
UV Drive	UV1	C2	1	2	1 ²
Valve, 3-way	TV1-1	B5	1	2 ³	
Valve, 3-way	TV1-4	C7	1	2 ³	
Valve, 3-way	TV1-5	C4	1	2 ³	
Valve, 3-way	TV1-6	C3	1	2 ³	
Valve, 3-way	TV1-9	B6	1	2 ³	
Valve, 3-way	SV1-2	B7	1	2 ³	
Valve, 3-way	SV1-3	B7	1	2 ³	
Valve, 3-way	SV1-4	D4	1	2 ³	
Condensate Detector	CD1	D4	1	1	
Total Channel Counts ¹			19	22	20

¹ Per Flow Diagram 7330168 Rev. G² not shown in Rev. G. to be added³ baseline assumes full position mitigation


PCWQM Overall Dimensions




PCWQM Top Front Panel View




PCWQM Top Rear Panel View




PCWQM Bottom Rear Left Panel View



PCWQM Bottom Rear Right Panel View






ORU3 = pH and Cal Standard Assembly


November 20, 1997

PCWQM Program & Design Status


z zeltweger analytics

pH Probe and Electronics Assembly






ORU2 = Solid Phase Acidifier Assembly




TIC/TOC Detector Assembly


UV Reactor Assembly




Pump/Motor Assembly



Pump Motor Electronics Assembly



Condensate Detector Assembly




November 20, 1997


PCWQM Program & Design Status


zellweger analytics

Assumed Firmware Controller Volume




ORU2 Interface Manifold Assembly





ORU3 Interface Manifold Assembly

Oxygen Manifold Assembly



PCWQM Future Technical Development

- Must establish Technical Baseline and Program Requirements!
- This directly impacts Cost & Schedule!
- Examples:
 - Class S -vs- Class B EEE Parts
 - Analyses detail (to what level(s), safety factors, etc.)
 - Testing -vs- Analyses
 - Amount of “Flow down” requirements that would have to be levied on our vendors
 - HSD/DCMO involvement in Assembly and Testing
 - MRB Responsibility